WHITETAIL DRIVE SUBDIVISION

1473 U.S. ROUTE ONE, FREEPORT, MAINE

PREPARED BY:

CIVIL ENGINEER/SURVEYOR: TERRADYN CONSULTANTS, LLC 41 CAMPUS DR. SUITE 101 NEW GLOUCESTER, MAINE 04260 (207) 926-5111

WETLANDS SURVEY:
BASSWOOD ENVIRONMENTAL
93 MILL ROAD
CAPE ELIZABETH, MAINE 04107
(207) 518-8442

SITE EVALUATOR:
MARK CENCI, GEOLOGIC, INC.
93 MILL ROAD
NORTH YARMOUTH, MAINE 04097
(207) 329-3524

APPLICANT/OWNER:

WILLIAM DAVENPORT & TODD HARRISON
321 AUBURN POWNAL ROAD
DURHAM MAINE 04222

PROJECT PARCEL SITE

FOWN OF FREEPORT TAX ASSESSOR'S MAP & LOT NUMBERS

MAP LOT

PROJECT SITE

1. SCATTOR ATTE

1. SCATTOR ATTER

1. SCATTOR

LOCATION MAP

SCALE: 1" = 200'

SHEET INDEX

C-1.0	COVER SHEET & LOCATION MAP
S-1.0	BOUNDARY SURVEY
C-2.0	SUBDIVISION RECORDING PLAN
C-3.0	SITE AND UTILITY PLAN
C-4.0	GRADING AND DRAINAGE PLAN
C-5.0	PROFILE: WHITETAIL DRIVE
C-5.1	MAINEDOT DETAIL
C-6.0	EROSION CONTROL DETAILS
C-6.1	SITE DETAILS & NOTES
C-6.2	STORMWATER DETAILS

LEGEND	
	EXISTING PROPERTY LINE
	PROPOSED PROPERTY LINE
	PROPOSED SETBACK LINE
	EXISTING SETBACK LINE
	EXISTING EASEMENT
- · - · - · - · -	PROPOSED EASEMENT
	ROAD CENTERLINE
124	EXISTING MINOR CONTOUR
124	EXISTING MAJOR CONTOUR
124	PROPOSED CONTOUR
SD	EXISTING STORMDRAIN
SD	PROPOSED STORMDRAIN
———OHE———	EXISTING OVERHEAD ELECTRIC & TELEPHONE
—— OHE ——	PROPOSED OVERHEAD ELECTRIC
	& TELEPHONE
UGE	EXISTING UNDERGROUND
	ELECTRIC & TELEPHONE
	PROPOSED UNDERGROUND
	ELECTRIC & TELEPHONE
	EXISTING EDGE OF PAVEMENT
	PROPOSED EDGE OF PAVEMENT
	EXISTING EDGE OF GRAVEL
	PROPOSED EDGE OF GRAVEL
mmmm	EXISTING TREE LINE
uuuuuu	PROPOSED TREE LINE
	CHAIN LINK FENCE
	PROPOSED FENCE
0 0 0	EXISTING GUARDRAIL
0 0 0 0	PROPOSED GUARDRAIL
——————————————————————————————————————	SILT FENCE
	PROPOSED TRANSFORMER
*	PROPOSED LIGHT POLE
-0-	EXISTING UTILITY POLE
-0-	PROPOSED UTILITY POLE
	PROPOSED CATCH BASIN
+ 30.20	EXISTING SPOT GRADE
_× 30.20	PROPOSED SPOT GRADE
-0	EXISTING SIGN
	PROPOSED SIGN
TP-A	TEST PIT
	EXISTING BUILDING
	PROPOSED BUILDING
<u> 111. 111.</u>	WETLAND AREA
	WETLAND DISTURBANCE
	PROPOSED PAVEMENT
	RIPRAP
	BUFFER
	EXPOSED LEDGE
	NON DISTUDBANCE STDEAM SETRA

NON-DISTURBANCE STREAM SETBACK AREA

PERMIT DRAWING NOT FOR CONSTRUCTION


SUBDIVISION


ETAIL DRIVE


01-09-2023 1" = 200' 22-57

C-0.0














01-31-2024


PERMIT DRAWING
NOT FOR CONSTRUCTION

HARRISON TODD ∞ర

DAVENPORT S

01-09-2023 AS SHOWN

22-57 C-5.0



2+00

1+00

PROFILE: WHITETAIL DRIVE

SCALE: 1" = 20' HORIZ.

1" = 2' VERT.

0+00

6.00'

HIGH POINT ELEV. 224.46

ENTRANCE DETAIL NOT TO SCALE

-0.5% ———

8.00'


BEGIN SAG CURVE PVC STA. 0+20, ELEV. 224.19

6.00'

EDGE OF SHOULDER STA. 0+00, ELEV 224.37

+1.5%

ROUTE 1 SHOULDER -1/2"/FT MAX —



01-09-2023

C-5.1

SHEET:

1" = 20' 22-57

EROSION AND SEDIMENT CONTROL PLAN

Pre-Construction Phase

materials shall take measures to prevent unreasonable erosion of soil or sediment beyond the project site or into a protected natural resource as defined in 38 mrsa § 480-b. Erosion control measures must be in place before the activity begins. Measures must remain in place and functional until the site is permanently stabilized. Adequate and timely temporary and permanent stabilization measures must be taken. The site must be maintained to prevent unreasonable erosion and sedimentation. Minimize disturbed areas and protect natural downgradient buffer areas to the extent practicable.

BMP Construction Phase

A. Sediment barriers. Prior to the beginning of any construction, properly install sediment barriers at the edge of any downgradient disturbed area and adjacent to any drainage channels within the proposed disturbed area. Maintain the sediment barriers until the disturbed area is permanently stabilized.

B. Construction entrance: Prior to any clearing or grubbing, a construction entrance shall be constructed at the intersection with the proposed access drive and the existing roadway to avoid tracking of mud, dust and debris from the site.

C. Riprap: Since riprap is used where erosion potential is high, construction must be sequenced so that the riprap is put in place with the minimum delay. Disturbance of areas where riprap is to be placed should be undertaken only when final preparation and placement of the riprap can follow immediately behind the initial disturbance. Where riprap is used for outlet protection, the riprap should be placed before or in conjunction with the construction of the pipe or channel so that it is in place C. Apply hay mulch at twice the standard rate (150 lbs. Per 1,000 sf). The mulch must be thick enough such that the when the pipe or channel begins to operate. Maintain temporary riprap, such as temporary check dams until the disturbed area is permanently stabilized.

D. Temporary stabilization. Stabilize with temporary seeding, mulch, or other non-erodable cover any exposed soils that will remain unworked for more than 14 days except, stabilize areas within 100 feet of a wetland or waterbody within 7 days or prior to a predicted storm event, whichever comes first. If hay or straw mulch is used, the application rate must be 2 bales (70-90 pounds) per 1000 sf or 1.5 to 2 tons (90-100 bales) per acre to cover 75 to 90% of the ground surface. Hay mulch must be kept moist or anchored to prevent wind blowing. An erosion control blanket or mat shall be used at the base of

grassed waterways, steep slopes (15% or greater) and on any disturbed soil within 100 feet of lakes, streams and wetlands. Grading shall be planned so as to minimize the length of time between initial soil exposure and final grading. On large projects G. Winter excavation and earthwork shall be completed so that no more than 1 acre of the site is without stabilization at this should be accomplished by phasing the operation and completing the first phase up to final grading and seeding before any one time. starting the second phase, and so on. Inspection and stabilization of temporary erosion and sedimentation control BMPs shall occur within 48 hours of a wet weather event. Stabilize areas within 75 feet of a wetland or waterbody within 48 hours of the H. An area within 100 feet of a protected natural resource must be protected with a double row of sediment barrier. initial disturbance of the soil or prior to any storm event, whichever comes first.

E. Vegetated waterway. Upon final grading, the disturbed areas shall be immediately seeded to permanent vegetation and mulched and will not be used as outlets until a dense, vigorous vegetative cover has been obtained. Once soil is exposed for waterway construction, it should be immediately shaped, graded and stabilized. Vegetated waterways need to be stabilized early during the growing season (prior to september 15). If final seeding of waterways is delayed past september 15, emergency provisions such as sod or riprap may be required to stabilize the channel. Waterways should be fully stabilized prior to directing runoff to them.

Permanent stabilization defined

A. Seeded areas. For seeded areas, permanent stabilization means an 90% cover of the disturbed area with mature, healthy plants with no evidence of washing or rilling of the topsoil.

B. Sodded areas. For sodded areas, permanent stabilization means the complete binding of the sod roots into the underlying soil with no slumping of the sod or die-off.

C. Permanent mulch. For mulched areas, permanent mulching means total coverage of the exposed area with an approved mulch material. Erosion control mix may be used as mulch for permanent stabilization according to the approved application rates and limitations.

D. Riprap. For areas stabilized with riprap, permanent stabilization means that slopes stabilized with riprap have an appropriate backing of a well-graded gravel or approved geotextile to prevent soil movement from behind the riprap. Stone must be sized appropriately. It is recommended that angular stone be used.

E. Agricultural use. For construction projects on land used for agricultural purposes (e.G., pipelines across crop land), permanent stabilization may be accomplished by returning the disturbed land to agricultural use.

F. Paved areas. For paved areas, permanent stabilization means the placement of the compacted gravel subbase is completed.

G. Ditches, channels, and swales. For open channels, permanent stabilization means the channel is stabilized with mature vegetation at least three inches in height, with well-graded riprap, or with another non-erosive lining capable of withstanding the anticipated flow velocities and flow depths without reliance on check dams to slow flow. There must be no evidence of slumping of the lining, undercutting of the banks, or down-cutting of the channel.

inspecting engineer.

The following erosion control measures shall be followed by the contractor throughout construction of this project: A. All topsoil shall be collected, stockpiled, seeded with rve at 3 pounds/1,000 sf and mulched, and reused as required. Silt fencing shall be placed down gradient from the stockpiled loam. Stockpile to be located by designation of the owner and

B. The inspecting engineer at his/her discretion, may require additional erosion control measures and/or supplemental vegetative provisions to maintain stability of earthworks and finish graded areas. The contractor shall be responsible for providing and installing any supplemental measures as directed by the inspecting engineer. Failure to comply with the engineer's directions will result in discontinuation of construction activities.

C. Erosion control mesh shall be applied in accordance with the plans over all finish seeded areas as specified on the design

D. All graded or disturbed areas including slopes shall be protected during clearing and construction in accordance with the approved erosion and sediment control plan until they are adequately stabilized.

the approved erosion and sediment control plan.

E. All erosion, and sediment control practices and measures shall be constructed, applied and maintained in accordance with

F. Areas to be filled shall be cleared, grubbed and stripped of topsoil to remove trees, vegetation, roots or other objectionable

G. Areas shall be scarified to a minimum depth of 3 inches prior to placement of topsoil.

H. All fills shall be compacted as required to reduce erosion, slippage, settlement, subsidence or other related problems. Fill intended to support buildings, structures and conduits, etc., shall be compacted in accordance with local requirements or

I. All fills shall be placed and compacted in layers not to exceed 8 inches in thickness.

J. Except for approved landfills or non-structural fills, fill material shall be free of brush, rubbish, rocks, logs, stumps, building debris and other objectionable materials that would interfere with or prevent construction of satisfactory lifts.

K. Frozen material or soft, mucky or highly compressible materials shall not be incorporated into fill slopes or structural fills.

L. Fill shall not be placed on a frozen foundation.

M. Seeps or springs encountered during construction shall be handled appropriately.

N. All graded areas shall be permanently stabilized immediately following finished grading.

O. Remove any temporary control measures, such as silt fence, within 30 days after permanent stabilization is attained. Remove any accumulated sediments and stabilize.

Permanent vegetative cover should be established on disturbed areas where permanent, long lived vegetative cover is needed to stabilize the soil, to reduce damages from sediment and runoff, and to enhance the environment.

A. Grade as feasible to permit the use of conventional equipment for seedbed preparation, seeding, mulch application and anchoring, and maintenance.

B. Apply limestone and fertilizer according to soil tests such as those offered by the university of maine soil testing laboratory. Soil sample mailers are available from the local cooperative extension service office. If soil testing is not feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 800 pounds per acre or 18.4 pounds per 1,000 square feet using 10-20-20 (n-p2o5-k2o) or equivalent. Apply ground limestone (equivalent to 50% calcium plus magnesium oxide) at

a rate of 3 tons per acre (138 lb. Per 1,000 sq. Ft).

C. Work lime and fertilizer into the soil as nearly as practical to a depth of 4 inches with a disc, spring tooth harrow or other suitable equipment. The final harrowing operation should be on the general contour. Continue tillage until a reasonably uniform, fine seedbed is prepared. All but clay or silty soils and coarse sands should be rolled to firm the seedbed wherever feasible.D. Remove from the surface all stones 2 inches or larger in any dimension. Remove all other debris, such as wire, cable, tree roots, concrete, clods, lumps or other unsuitable material.

E. Inspect seedbed just before seeding. If traffic has left the soil compacted; the area must be tilled and firmed as above.

F. Permanent seeding should be made 45 days prior to the first killing frost or as a dormant seeding with mulch after the first killing frost and before snowfall. When crown vetch is seeded in later summer, at least 35% of the seed should be hard seed (unscarified). If seeding cannot be done within the seeding dates, mulch according to the temporary mulching bmp and overwinter stabilization and construction to protect the site and delay seeding until the next recommended seeding period.

A person who conducts, or causes to be conducted, an activity that involves filling, displacing or exposing soil or other earthen G. Following seed bed prepartation, swale areas, fill areas and back slopes shall be seeded at a rate of 3 lbs./1,000 s.F. With a mixture of 35% creeping red h. Fescue, 6% red top, 24% kentucky bluegrass, 10% perennial ryegrass, 20% annual ryegrass and 5% white dutch clover.

I. Areas which have been temporarily or permanently seeded shall be mulched immediately following seeding.

J. Areas which cannot be seeded within the growing season shall be mulched for over-winter protection and the area should be seeded at the beginning of the growing season.

Winter construction phase

If an area is not stabilized with temporary or permanent measures by november 15, then the site must be protected with additional stabilization measures.

A. Permanent stabilization consists of at least 90% vegetation, pavement/gravel base or riprap.

B. Do not expose slopes or leave slopes exposed over the winter or for any other extended time of work suspension unless fully protected with mulch.

ground surface will not be visible and must be anchored.

D. Use mulch and mulch netting or an erosion control mulch blanket or all slopes greater than 8 % or other areas

E. Install an erosion control blanket in all drainageways (bottom and sides) with a slope greater than 3 %.

F. See the vegetation measures for more information on seeding dates and types.

I. Temporary mulch must be applied within 7 days of soil exposure or prior to any storm event, but after every workday in areas within 100 feet from a protected natural resource.

J. Areas that have been brought to final grade must be permanently mulched that same day.

K. If snowfall is greater than 1 inch (fresh or cumulative), the snow shall be removed from the areas due to be seeded


L. Loam shall be free of frozen clumps before it is applied.

M. All vegetated ditch lines that have not been stabilized by november 1, or will be worked during the winter construction period, must be stabilized with an appropriate stone lining backed by an appropriate gravel bed or geotextile unless specifically released from this standard by the department.

Maintenance and inspection phase

A. Contractor shall inspect disturbed and impervious areas, and erosion and stormwater control measures, areas used for storage that are exposed to precipitation, and locations where vehicles enter or exit the parcel at least once a week and before and after a storm event, prior to completion of permanent stabilization. A storm event triggering the need for inspection during construction is defined as 0.5" of rainfall. A person with knowledge of erosion and stormwater must conduct the inspection. This person must be identified in the inspection log. If best management practices (bmps) need to be modified or if additional bmps are necessary, implementation must be completed within 7 calendar days and prior to any storm event (rainfall). All measures must be maintained in effective operating condition until areas are permanently stabilized.

B. A log (report) must be kept summarizing the scope of the inspection, name(s) and qualifications of the personnel making the inspection, the date(s) of the inspection, and major observations relating to operation of erosion and sedimentation controls and pollution prevention measures. Major observations must include: bmps that need to be maintained; location(s) of bmps that failed to operate as designed or proved inadequate for a particular location; and location(s) where additional bmps are needed that did not exist at the time of inspection. Follow-up to correct deficiencies or enhance controls must also be indicated in the log and dated, including what action was taken and when.




1. 'La' = LENGTH OF APRON. DISTANCE 'La' SHALL BE OF SUFFICIENT

LENGTH TO DISSIPATE ENERGY.

2. APRON SHALL BE SET AT A ZERO GRADE AND ALIGNED STRAIGHT.

3. FILTER MATERIAL SHALL BE FILTER FABRIC (MIRAFI 600X OR APPROVED EQUAL) OR 6" (150mm) THICK MINIMUM GRADED GRAVEL LAYER.

PIPE OUTLET PROTECTION NOT TO SCALE



1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT.


-50' MINIMUM

- DIVERSION RIDGE

MIN. 6" (150mm) THICK

2. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. 3. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

> STABILIZED CONSTRUCTION ENTRANCE NOT TO SCALE





BURY THE TOP END OF THE MESH MATERIAL IN A 6" TRENCH AND BACKFILL AND TAMP TRENCHING SECURE END


2. FLOW DIRECTION JOINTS TO HAVE UPPER END OF LOWER STRIP BURIED WITH UPPER LAYERS OVERLAPPED 4" AND

3. LATERAL JOINTS TO HAVE 4" OVERLAP OF STRIPS. STAPLE 18" ON CENTER.

GREEN VMAX SC250 PERMANENT TURF REINFORCEMENT MAT (OR APPROVED EQUAL) ON SLOPES 2:1 AND STEEPER..








EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES & MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE FOLLOWING STANDARDS: - THE ORGANIC MATTER CONTENT SHALL BE BETWEEN 80% - 100% DRY WEIGHT BASIS - PARTICLE SIZE BY WEIGHT SHALL BE 100% PASSING A 6" SCREEN AND A MINIMUM OF 70%, MAXIMUM OF 85% PASSING A 0.75" SCREEN


- THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED - LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX. - SOLUBLE SALTS CONTENT SHALL BE < 4.0 mmhos/cm. - ph SHALL FALL BETWEEN 5.0 - 8.0.

EROSION CONTROL MIX BERM



FILTER SOCK

NOT TO SCALE



SUBDIVISION RIVE 01-09-2023


C-6.0

22-57


SCALE: JOB NO:


MATERIAL SPREAD OUT ONTO THE GROUND. THE MESH MATERIAL

SHOULD BE REMOVED.



TYPICAL PAVEMENT JOINT





50' R.O.W.

18-0" WIDTH

9-0"

1/4 "/FT

3" CRUSHED AGGREGATE BASE COURSE -

(M.D.O.T. SPEC. 703.06 (a) TYPE A)

(M.D.O.T. SPEC. 703.06 (b) TYPE D)

12" AGGREGATE SUBBASE —

1" HMA SURFACE PAVEMENT (9.5mm) ———

2" HMA BINDER PAVEMENT (19mm)

9-0"

1/4 "/FT

COMMON BORROW, SEE NOTE

NOTE: FILL AREAS BENEATH DRIVING SURFACE SHALL BE GRANULAR BORROW. ALL OTHER FILL AREAS SHALL BE A

PERISHABLE RUBBLE, PEAT, ORGANICS, ROCKS LARGER THAN 12" IN DIAMETER, VEGETATION AND OTHER MATERIAL

UNSUITABLE FOR ROADWAY AND SUB-GRADE CONSTRUCTION. EXCAVATED ONSITE MATERIALS MAY BE USED FOR FILL

PROVIDED THE MATERIAL IS FREE FROM UNSUITABLE MATERIAL DESCRIBED IN THIS NOTE AND UPON APPROVAL OF

THE ENGINEER. GRANULAR BORROW AND COMMON BORROW SHALL ADHERE TO MDOT SPECIFICATIONS 703.19 AND

PRIVATE ROAD DEAD-END SECTION

COMMON BORROW MATERIAL SUITABLE FOR EMBANKMENT CONSTRUCTION, FREE FROM FROZEN MATERIAL,

GRAVFI

SHLDR.

1/2 "/FT

EXISTING-

GROUND

4" LOAM, SEED —

- PLACE GEOTEXTILE FABRIC

MINIMUM OF 10' PAST THE

EQUAL) EXTENDING A

(MIRIFI 600 X OR APPROVED

LIMIT OF WETLAND CROSSING

& MULCH (TYP)

- 4" LOAM,

∠ 6' WIDE

FROSION

CONTROL

BLANKET

BOTTOM OF

OF SUBBASE

DITCH TO BE 6"


BELOW BOTTOM


703.18 RESPECTIVELY.


SEED & MULCH


GRAVEL


SHLDR.













NOT TO SCALE





CONSTRUCTION NOTES

1. ALL WORK SHALL CONFORM TO THE APPLICABLE CODES AND ORDINANCES.

2. CONTRACTOR SHALL VISIT THE SITE AND FAMILIARIZE HIM OR HERSELF WITH ALL CONDITIONS AFFECTING THE PROPOSED WORK AND SHALL MAKE PROVISIONS AS TO THE COST THEREOF. CONTRACTOR SHALL BE RESPONSIBLE FOR FAMILIARIZING HIM OR HERSELF WITH ALL CONTRACT DOCUMENTS, FIELD CONDITIONS AND DIMENSIONS AND CONFIRMING THAT THE WORK MAY BE ACCOMPLISHED AS SHOWN PRIOR TO PROCEEDING WITH CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER PRIOR TO THE COMMENCEMENT OF WORK.

3. CONTRACTOR SHALL NOTIFY ENGINEER OF ALL PRODUCTS OR ITEMS NOTED AS "EXISTING" WHICH ARE NOT FOUND IN THE FIELD.

4. INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND OWNER'S REQUIREMENTS UNLESS SPECIFICALLY OTHERWISE INDICATED OR WHERE LOCAL CODES OR REGULATIONS TAKE PRECEDENCE.

5. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO FABRICATION AND ERECTION OF ANY MATERIAL. ANY UNUSUAL CONDITIONS SHALL BE REPORTED TO THE ATTENTION OF THE ENGINEER.

6. CONTRACTOR SHALL CLEAN AND REMOVE DEBRIS AND SEDIMENT DEPOSITED ON PUBLIC STREETS, SIDEWALKS, ADJACENT AREAS, OR OTHER PUBLIC WAYS DUE TO CONSTRUCTION.

7. CONTRACTOR SHALL INCORPORATE PROVISIONS AS NECESSARY IN CONSTRUCTION TO PROTECT EXISTING STRUCTURES, PHYSICAL FEATURES, AND MAINTAIN SITE STABILITY DURING CONSTRUCTION. CONTRACTOR SHALL RESTORE ALL AREAS TO ORIGINAL CONDITION AND AS DIRECTED BY DESIGN DRAWINGS.

8. SITE CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS PRIOR TO CONSTRUCTION.

9. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH "MAINE EROSION AND SEDIMENTATION CONTROL HANDBOOK FOR CONSTRUCTION: BEST MANAGEMENT PRACTICES" PUBLISHED BY THE CUMBERLAND COUNTY SOIL AND WATER CONSERVATION DISTRICT AND MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION, MARCH 2016 OR LATEST EDITION. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO POSSESS A COPY OF THE EROSION CONTROL PLAN AT ALL TIMES

10. THE CONTRACTOR IS HEREBY CAUTIONED THAT ALL SITE FEATURES SHOWN HEREON ARE BASED ON FIELD OBSERVATIONS BY THE SURVEYOR AND BY INFORMATION PROVIDED BY UTILITY COMPANIES. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR SHALL CONTACT DIG SAFE (1-888-DIGSAFE) AT LEAST THREE (3) BUT NOT MORE THAN THIRTY (30) DAYS PRIOR TO COMMENCEMENT OF EXCAVATION OR DEMOLITION TO VERIFY HORIZONTAL AND VERTICAL LOCATION OF AL

11. CONTRACTOR SHALL BE AWARE THAT DIG SAFE ONLY NOTIFIES ITS "MEMBER" UTILITIES ABOUT THE DIG. WHEN NOTIFIED, DIG SAFE WILL ADVISE CONTRACTOR OF MEMBER UTILITIES IN THE AREA. CONTRACTOR IS RESPONSIBLE FOR IDENTIFYING AND CONTACTING NON-MEMBER UTILITIES DIRECTLY. NON-MEMBER UTILITIES MAY INCLUDE TOWN OR CITY WATER AND SEWER DISTRICTS AND SMALL LOCAL UTILITIES, AS WELL AS USG PUBLIC WORKS SYSTEMS.

12. CONTRACTORS SHALL BE RESPONSIBLE FOR COMPLIANCE WITH THE REQUIREMENTS OF 23 MRSA 3360-A. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WITH THE APPROPRIATE UTILITIES TO OBTAIN AUTHORIZATION PRIOR TO RELOCATION OF ANY EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS. IF A UTILITY CONFLICT ARISES, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE OWNER, THE MUNICIPALITY AND APPROPRIATE UTILITY COMPANY PRIOR TO PROCEEDING WITH ANY RELOCATION.

13. ALL PAVEMENT MARKINGS AND DIRECTIONAL SIGNAGE SHOWN ON THE PLAN SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) STANDARDS.

14. ALL PAVEMENT JOINTS SHALL BE SAWCUT PRIOR TO PAVING TO PROVIDE A DURABLE AND UNIFORM

15. NO HOLES, TRENCHES OR STRUCTURES SHALL BE LEFT OPEN OVERNIGHT IN ANY EXCAVATION ACCESSIBLE TO THE PUBLIC OR IN PUBLIC RIGHTS-OF-WAY.

16. ALL WORK WITHIN THE PUBLIC RIGHT-OF-WAY SHALL REQUIRE A M.D.O.T. PERMIT AS WELL AS PERMITS FROM THE TOWN AS APPLICABLE

17. THE PROPOSED LIMITS OF CLEARING SHOWN HEREON ARE APPROXIMATE BASED UPON THE PROPOSED LIMITS OF SITE GRADING. THE APPLICANT RESERVES THE RIGHT TO PERFORM NORMAL FOREST MANAGEMENT ACTIVITIES OUTSIDE OF THE CLEARING LIMIT AS SHOWN. TREE REMOVAL OUTSIDE OF THE LIMITS OF CLEARING MAY BE NECESSARY TO REMOVE DEAD OR DYING TREES OR TREE LIMBS. THIS REMOVAL IS DUE TO POTENTIAL SAFETY HAZARDS AND TO PROMOTE PROPER FOREST GROWTH.

18. IMMEDIATELY UPON COMPLETION OF CUTS/FILLS, THE CONTRACTOR SHALL STABILIZE DISTURBED AREAS IN ACCORDANCE WITH EROSION CONTROL NOTES AND AS SPECIFIED ON PLANS.

19. THE CONTRACTOR SHALL BE FULLY AND SOLELY RESPONSIBLE FOR THE REMOVAL, REPLACEMENT AND RECTIFICATION OF ALL DAMAGED AND DEFECTIVE MATERIAL AND WORKMANSHIP IN CONNECTION WITH THE CONTRACT WORK. THE CONTRACTOR SHALL REPLACE OR REPAIR AS DIRECTED BY THE OWNER ALL SUCH DAMAGED OR DEFECTIVE MATERIALS WHICH APPEAR WITHIN A PERIOD OF ONE YEAR FROM THE DATE OF SUBSTANTIAL COMPLETION.

20. ALL WORK PERFORMED BY THE GENERAL CONTRACTOR AND/OR TRADE SUBCONTRACTOR SHALL CONFORM TO THE REQUIREMENTS OF LOCAL, STATE OR FEDERAL LAWS, AS WELL AS ANY OTHER GOVERNING REQUIREMENTS, WHETHER OR NOT SPECIFIED ON THE DRAWINGS.

21. WHERE THE TERMS "APPROVED EQUAL", "OTHER APPROVED", "EQUAL TO", "ACCEPTABLE" OR OTHER GENERAL QUALIFYING TERMS ARE USED IN THESE NOTES, IT SHALL BE UNDERSTOOD THAT REFERENCE IS MADE TO THE RULING AND JUDGMENT OF TERRADYN CONSULTANTS, LLC.

22. THE GENERAL CONTRACTOR SHALL PROVIDE ALL NECESSARY PROTECTION FOR THE WORK UNTIL TURNED OVER TO THE OWNER.


23. THE GENERAL CONTRACTOR SHALL MAINTAIN A CURRENT AND COMPLETE SET OF CONSTRUCTION DRAWINGS ON SITE DURING ALL PHASES OF CONSTRUCTION FOR USE OF ALL TRADES.

24. THE CONTRACTOR SHALL TAKE FULL RESPONSIBILITY FOR ANY CHANGES AND DEVIATION OF APPROVED PLANS NOT AUTHORIZED BY THE ARCHITECT/ENGINEER AND/OR CLIENT/OWNER.

25. DETAILS ARE INTENDED TO SHOW END RESULT OF DESIGN. ANY MODIFICATION TO SUIT FIELD DIMENSION

AND CONDITION SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ANY WORK.

26. BEFORE THE FINAL ACCEPTANCE OF THE PROJECT, THE CONTRACTOR SHALL REMOVE ALL EQUIPMENT AND MATERIALS, REPAIR OR REPLACE PRIVATE OR PUBLIC PROPERTY WHICH MAY HAVE BEEN DAMAGED OR DESTROYED DURING CONSTRUCTION, CLEAN THE AREAS WITHIN AND ADJACENT TO THE PROJECT WHICH HAVE BEEN OBSTRUCTED BY HIS/HER OPERATIONS, AND LEAVE THE PROJECT AREA NEAT AND PRESENTABLE.



01-31-2024

PERMIT DRAWING NOT FOR CONSTRUCTION

AIL F

01-09-2023


22-57

DATE: SCALE: JOB NO:

SUBDI

DRIVE

C-6.



REPM CONSTRUCTION

THE BERM MUST BE WELL-GRADED AND CONTAIN SOME SMALL STONE AND GRAVEL SO THAT FLOW THROUGHT THE BERM WILL BE RESTRICTED ENOUGH TO CAUSE IT TO SPREAD OUT BEHIND THE

- 2. A 6 INCH DEEP TRAPEZOIDAL TROUGH WITH A MINIMUM BOTTOM WIDTH OF 3 FEET MUST BE CONSTRUCTED WITH A LEVEL DOWNHILL EDGE EXCAVATED ALONG THE CONTOUR ON THE UPHILL EDGE OF THE STONE BERM.
- 3. THE STONE MUST BE COARSE ENOUGH THAT IT WILL NOT CLOG WITH SEDIMENT. STONE MUST CONSIST OF SOUND DURABLE ROCK THAT WILL NOT DISINTEGRATE BY EXPOSURE TO WATER OR WEATHER. FIELDSTONE, ROUGH QUARRIED STONE, BLASTED LEDGE ROCK OR TAILINGS MAY BE USED. THE ROCK MUST BE WELL GRADED WITH A MEDIAN SIZE OF APPROXIMATELY 3 INCHES AND A MAXIMUM SIZE OF 6 INCHES PER THE FOLLOWING TABLE.

BERM STONE SIZE					
SIEVE	% PASSING BY WEIGHT				
12"	100%				
6"	84% - 100%				
3"	68% - 83%				
1"	42% - 55%				
NO. 4	8% - 12%				

STONE BERMED LEVEL LIP SPREADER

NOT TO SCALE

- CONSTRUCTION OVERSIGHT NOTES:

 1. CONSTRUCTION OVERSIGHT: INSPECTION BY A PROFESSIONAL ENGINEER WILL OCCUR AT A MINIMUM:
- MINIMUM:

 AFTER THE PRELIMINARY CONSTRUCTION OF THE FILTER GRADES AND ONCE THE
- AFTER THE DRAINAGE LAYER IS CONSTRUCTED AND PRIOR TO THE INSTALLATION OF THE FILTER MEDIA,
- AFTER THE FILTER MEDIA HAS BEEN INSTALLED, PLANTED, AND MULCHED. BIO-RETENTION CELLS MUST BE STABILIZED PER THE PROVIDED PLANTING SCHEME AND DENSITY FOR THE CANOPY COVERAGE OF 30 AND 50%.

AFTER ONE YEAR TO INSPECT HEALTH OF THE VEGETATION AND MAKE CORRECTIONS.

2. ALL THE MATERIAL USED FOR THE CONSTRUCTION OF THE FILTER BASIN MUST BE CONFIRMED AS SUITABLE BY THE DESIGN ENGINEER. TESTING MUST BE DONE BY A

UNDERDRAIN PIPES ARE INSTALLED BUT NOT BACKFILLED,

- CERTIFIED LABORATORY TO SHOW THAT THEY ARE PASSING DEP SPECIFICATIONS.

 3. TESTING AND SUBMITTALS: THE CONTRACTOR SHALL IDENTIFY THE LOCATION OF THE SOURCE OF EACH COMPONENT OF THE FILTER MEDIA. ALL RESULTS OF FIELD AND
- LABORATORY TESTING SHALL BE SUBMITTED TO THE PROJECT ENGINEER FOR CONFIRMATION. THE CONTRACTOR SHALL:

 SELECT SAMPLES FOR SAMPLING OF EACH TYPE OF MATERIAL TO BE BLENDED FOR THE MIXED FILTER MEDIA AND SAMPLES OF THE UNDERDRAIN BEDDING MATERIAL. SAMPLES
- MUST BE A COMPOSITE OF THREE DIFFERENT LOCATIONS (GRABS) FROM THE STOCKPILE OR PIT FACE. SAMPLE SIZE REQUIRED WILL BE DETERMINED BY THE TESTING LABORATORY.

 PERFORM A SIEVE ANALYSIS CONFORMING TO STM C136 (STANDARD TEST METHOD FOR SIEVE ANALYSIS OF FINE AND COURSE AGGREGATES 1996A) ON EACH TYPE OF THE

SAMPLE MATERIAL. THE RESULTING SOIL FILTER MEDIA MIXTURE MUST HAVE 8% TO 12%

BY WEIGHT PASSING THE #200 SIEVE, A CLAY CONTENT OF LESS THAN 2% (DETERMINED

HYDROMETER GRAIN SIZE ANALYSIS) AND HAVE 10% DRY WEIGHT OF ORGANIC MATTER.

• PERFORM A PERMEABILITY TEST ON THE SOIL FILTER MEDIA MIXTURE CONFORMING TO ASTM D2434 WITH THE MIXTURE COMPACTED TO 90-92% OF MAXIMUM DRY DENSITY


ONOTPHOTION PHACE NOTES

CONSTRUCTION SEQUENCE: THE SOIL FILTER MEDIA AND VEGETATION MUST NOT BE INSTALLED UNTIL THE AREA THAT DRAINS TO THE FILTER HAS BEEN PERMANENTLY STABILIZED WITH PAVEMENT OR OTHER STRUCTURE, 90% VEGETATION COVER, OR OTHER PERMANENT STABILIZATION UNLESS THE RUNOFF FROM THE CONTRIBUTING DRAINAGE AREA IS DIVERTED AROUND THE FILTER UNTIL STABILIZATION IS COMPLETED.

COMPACTION OF SOIL FILTER: FILTER SOIL MEDIA AND UNDERDRAIN BEDDING MATERIAL MUST BE COMPACTED TO BETWEEN 90% AND 92% STANDARD PROCTOR. THE BED SHOULD BE INSTALLED IN AT LEAST 2 LIFTS OF 9 INCHES TO PREVENT POCKETS OF LOOSE MEDIA. OVERCOMPACTION SHOULD BE AVOIDED.

ADJUST DRAWDOWN TIME: AFTER THE FILTER BASIN IS STABILIZED, THE CONTRACTOR SHALL FILL THE BASIN UP TO THE ELEVATION OF THE WATER QUALITY VOLUME WITH CLEAN WATER AND ADJUST THE BALL VALVE TO ACHIEVE A 24-32 HR. RELEASE TIME.

UNDERDRAINED SOIL FILTER SCHEDULE				
A	TOP OF BERM ELEV.	228.34		
B	SPILLWAY ELEV.	227		
(C)	SURFACE ELEV.	225.5		
D	WATER QUALITY ELEV.	227		
	FILTER SURFACE AREA (SF)	1,227		
	WATER QUALITY VOLUME (CF)	2,415		





FILTER BASIN


THE FILTER LAYER AND TOPSOIL LAYER SHALL MEET THE GRADATION REQUIREMENTS IN THE TABLES BELOW AND SHALL CONTAIN LESS THAN 2% CLAY CONTENT, AS DETERMINED BY HYDROMETER TESTING


- 2. COMPACTION OF THE FILTER AND TOPSOIL LAYERS SHALL BE COMPLETED PRIOR TO SEEDING OR SODDING.
- 3. A DENSE COVER OF GRASS OR SOD SHALL BE ESTABLISHED AND MAINTAINED ON THE SURFACE TO PREVENT CLOGGING.
- 4. PLACE NON WOVEN GEOTEXTILE FABRIC (MIRIFI 140N OR APPROVED EQUAL) ON ALL SIDES AND BOTTOM OF SOIL & GRAVEL FILTER AREA.
- 5. THE BOTTOM OF THE FILTER BASIN SHALL BE PLANTED WITH THE FOLLOWING SEED MIXTURE OR APPROVED
- 6. THE CONTRACTOR SHALL CONDUCT A TEST PIT IN THE FILTER AREA IN THE PRESENCE OF CERTIFIED SOIL SCIENTIST PRIOR TO CONSTRUCTION OF THE BASIN TO DETERMINE THE SEASONAL HIGH GROUNDWATER ELEVATION. A PVC LINER MUST BE INSTALLED AS SHOWN ON THE DETAIL AND MUST EXTEND UP THE SIDES OF THE BASIN TO AN ELEVATION 6" ABOVE THE SEASONAL HIGH GW ELEVATION. IF BEDROCK IS ENCOUNTERED BEFORE EVIDENCE OF GROUNDWATER, THE LINER MUST BE INSTALLED UP TO THE WATER QUALITY ELEVATION. THE RESULTS OF THE TEST PIT AND ANY NECESARY CHANGES TO THE DESIGN SHALL BE SUBMITTED TO MDEP PRIOR TO CONSTRUCTION OF THE FILTER


LOAMY COARSE SAND (12" FILTER LAYER)		LOAMY TOPSOIL (6" TOP LAYER)	
SIEVE#	% PASSING BY WEIGHT	SIEVE#	% PASSING BY WEIGHT
10	85-100	4	75-95
20	70-100	10	60-90
60	15-40	40	38-85
200	8-15	200	20-70











01-09-2023

C-6.2

22-57

01-31-2024

